

**BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE**

Executive Engineer  
Byatarayanapura Division  
B.B.M.P., Bangalore - 92

**DRAFT TENDER SCHEDULE**

Issued to :

Original / Duplicate

Name of the work: Estimate for Maintainance of Elumandamma badavane BBMP Building and Gym Equipments in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division.

| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit | Rates      |          |
|---------|-----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------|
|         |           |                                                                                                                                                                                                                                                                                                                                                                                                                                    |      | In Figures | In Words |
| 1       | 307.50    | Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work                          | Sqm  | 90.10      |          |
| 2       | 373.40    | Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications with Primer etc complete as per specifications and directions of engineer in charge of the work | Cum  | 83.74      |          |
| 3       | 21.24     | Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work                                                                      | Sqm  | 87.48      |          |
| 4       | 50.00     | <b>Groove Cutting</b> : Supplying ... dia 2mm/2.5mm thick heavy gauage PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 32 mm dia 2.5mm thick etc complete as per specifications and directions of engineer in charge of the work         | Mtrs | 68.00      |          |
| 5       | 2         | Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work 10"X7"X3" (300X228X76mm) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                         | Each | 68.00      |          |
| 6       | 2         | 8"X6"X3" (300X228X76mm)                                                                                                                                                                                                                                                                                                                                                                                                            | Cum  | 52.00      |          |
| 7       | 5         | Supplying and fixing PVC/metal conduit accessories special type 32 mm Junction Box etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                             | Each | 29.00      |          |
| 8       | 2         | Deep 32 mm Junction Box                                                                                                                                                                                                                                                                                                                                                                                                            |      | 33.00      |          |


| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Unit | Rates      |          |
|---------|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------|
|         |           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      | In Figures | In Words |
| 9       | 5         | Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet Point Wiring using Class A Materials a) Short point upto 3Mtr from tapping point to out let via switch etc complete as per specifications and directions of engineer in charge of the work | Each | 175.00     |          |
| 10      | 2         | b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      | 260.00     |          |
| 11      | 3         | C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      | 368.00     |          |
| 12      | 30        | Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate 6Amps one way etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                     | Each | 96.00      |          |
| 13      | 15        | 6Amps 3way Socket.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      | 165.00     |          |
| 14      | 6         | Stepped Fan Regulator                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      | 520.00     |          |
| 15      | 5         | Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluourescent tube Group 'A' etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                          |      | 380.00     |          |
| 16      | 2         | Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system KPWD SR 2007-08 (P-23, I-23) Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard 56" Sweep (1400 mm) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                  | Each | 1950.00    |          |
| 17      | 2         | Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncessary supporting back plate with required nos. of machines screws, bolts nuts etc., complete on the existing metal/PVC box 1 to 3 Modular etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                   | Each | 82.00      |          |
| 18      | 3         | 8 Modular                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | 175.00     |          |
| 19      | 4         | Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate 6Amps one way etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                     | Each | 96.00      |          |
| 20      | 3         | 6Amps 3way Socket.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      | 165.00     |          |
| 21      | 2         | Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box Group A etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                           | Each | 630.00     |          |

| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Unit | Rates      |          |
|---------|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------|
|         |           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      | In Figures | In Words |
| 22      | 1         | Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                      | No   | 60.00      |          |
| 23      | 1         | Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required <b>5-32 Amps SP</b> etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                      | Each | 560.00     |          |
| 24      | 1         | Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20"x20"x2.5" etc etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                         | Each | 285.00     |          |
| 25      | 2         | Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers 32 Amps etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                         | Each | 100.00     |          |
| 26      | 10.00     | Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvanised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                              | Mtr  | 150.00     |          |
| 27      | 10.00     | Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, <b>P No. 69 / I No. 1a In existing trencg/duct 6Sqmm to 16 Sqmm</b> ) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                       | Mtr  | 8.00       |          |
| 28      | 8.00      | Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                     | Mtr  | 60.00      |          |
| 29      | 4.00      | Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm dia GI pipe etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                   | Mtr  | 240.00     |          |
| 30      | 1         | Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers 16Sqmm etc., etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                      | No.  | 260.00     |          |
| 31      | 1         | Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, etc complete as per specifications and directions of engineer in charge of the work | No   | 1950.00    |          |

| Sl. No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Unit | Rates      |          |
|---------|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------|
|         |           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      | In Figures | In Words |
| 32      | 1         | Supplying and fixing of GS 478 – Adjustable Bench with Main Frame and Strength training Oval steel tube, thickness (12 gauge), Solid Steel, Stack bushing – PVC cushion guided rods, Nylon with bearing Pulleys, High Strength cable has high load carrying capacity, smooth, even functioning of the workouts achieved, high life, M8, M10, M12 Bolts, Shining Silver, Powder coated painting, Orange fabric, High density virgin foam and Composite ply board with adjustable seat etc., complete as per Engineer in Charge of the work. | Nos  | 28692.49   |          |
| 33      | 1         | Supplying and fixing of GS-897 Flat Bench with 4x2 assembly area, 2/2 12 gauge PVC Pipe, Seat & High cashion red color H2x1Wx4L, 8 kg weight etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                         | Nos  | 12516.06   |          |
| 34      | 1         | Supplying and fixing of GS-899 Calf Bench of 2Hx2Wx5L assembly area, shining silver powder coated, high quality red color seat, of size 2/2.12 Gauge PVC pipe, 4 kg weight, bearing high quality seated bearing etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                      | Nos  | 36556.35   |          |
| 35      | 1         | Supplying and fixing of GS-759 Shoulder Bench of 2Lx2Wx4H Assembly area with 2/2 12 gauge PVC pipe, High Quality Red Shing Seat, 6 Kg Unit weight etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                    | Nos  | 7674.94    |          |
| 36      | 1         | Supplying and fixing of SP-102 T-Bar Row machine of 7Lx2Hx3W with 2/2 12 gauge PVC Pipe, 120 kg capacity, 20 kg weight, high quality shield bearing etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                  | Nos  | 28692.49   |          |
| 37      | 1         | Supplying and fixing of SP-102 Small Bench of 2Hx2Wx2L high quality red shining seat, 2/2 12 gauge PVC Pipe, 4 kgs weight etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                                            | Nos  | 5903.80    |          |
| 38      | 300.00    | Supplying and fixing of S305-Chrome dumbbles, Hand Grip Rubber bolt 'L' n Bol, high quality Ms Metal used, Nichal chrome used for shining, high grade knurling for seare comfortable gripping surface encased is high quality virgin metal dumbles are stable for fitness junkides 'b' coze they provide unmatched vorsebility etc., complete as per Engineer in Charge of the work.                                                                                                                                                       | Kgs  | 265.67     |          |
| 39      | 250.00    | Supplying and fixing of S125 Rubber Weight Plate of beauty chrome handles resist chipping, flaking, peeling and corrosion, medium grade knurling for a secure, comfortable gripping surface, rubber encased coating is high quality virgin rubber, plates are one of the most versatile and effective training tools and can be utilized to work your shoulders, triceps, biceps, legs and even your back etc., complete as per Engineer in Charge of the work.                                                                            | Kgs  | 265.67     |          |
| 40      | 2         | Supplying and fixing of SP 104 Plate Stand of 4Hx3Wx2L assembly area with shining Silver powder coated, 7 rod holder of 20 kg weight etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                                 | Nos  | 14995.66   |          |
| 41      | 2         | Supplying and fixing of SP 105 barbell stand of 1.5Lx1.5Wx1H with shining silver powder coated, 10 rod holders of 13 kg weight and 12mm thickness etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                                                    | Nos  | 9564.16    |          |
| 42      | 2         | Supplying and fixing of ACS03 Dumb bell Stand of 3Hx2Wx5L Assembly area with shining silver powder coated of 25 kg and 2/2 12 Gase 7& L Ange 1.5/6 PVC pipe and M01 belt etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                                                                                                             | Nos  | 18703.25   |          |

| Sl No. | Quantity. | Description                                                                                                                                                                                                                                                                                                                                                                         | Unit | Rates      |          |
|--------|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------|
|        |           |                                                                                                                                                                                                                                                                                                                                                                                     |      | In Figures | In Words |
| 43     | 10        | Supplying and fixing of Yoga Mat of 2x5 size 10mm, medium grade for a secure comfortable encased high quality virgin rubber mat etc., complete as per Engineer in Charge of the work..                                                                                                                                                                                              | Nos  | 708.46     |          |
| 44     | 5         | Supplying and fixing of Barbell Rods of 8kgs 4 ft and 5ft length, Nichal chrome used for shining medium grade knurling for a secure, comfortable gripping surface, ms steel 28mm solid rod etc., complete as per Engineer in Charge of the work.                                                                                                                                    | Nos  | 826.53     |          |
| 45     | 10        | Supplying and fixing of PUSH UP DIP STAND of 1 kg 1ft length, 12 gauge PVC pipe, high quality MS metal used etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                                   | Nos  | 2361.52    |          |
| 46     | 5         | Supplying and fixing of ANKEL WEIGHTS with 2 kgs wiehgt and 1ft length of comfortable gripping surface nylon encased coating etc., complete as per Engineer in Charge of the work.                                                                                                                                                                                                  | Kgs  | 944.61     |          |
| 47     | 7         | Supplying and fixing of Triceps handle high quality Ms Metal used Nichal chrome used for shining, high grade knurling for seare comfortable gripping surface encased is high quality virgin metal dumbles are stable for fitness junkides b coze and they provide unmatched vorsebily with 2 kgs size 2 ft length unit weight etc., complete as per Engineer in Charge of the work. | Nos  | 2361.52    |          |

Signature of the Contractor

  
Executive Engineer  
Byatarayanapura Division  
BBMP, Bangalore - 92

  
ಕರಡು ಬೆಂಡರ್ ಪಡ್ಯೂಲ್ನ್ನು  
ಶಿಡ್ಡುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )  
ಶಿಡ್ಡುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ  
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ  
  
ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು  
ಯಲಹಂಕ ವಲಯ  
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ  
ಬೆಂಗಳೂರು - 92